



VILLAGE OF MAPLE PARK

302 Willow Street • P.O. Box 220 • Maple Park, Illinois 60151
Village Hall: (815) 827-3309 • Fax: (815) 827-4040
Emergency: Police • Fire • Ambulance • Call 911

INFRASTRUCTURE COMMITTEE

March 9, 2010

A. FLOODING REMEDIATION

1. Northeastern Quadrant:
 - a. North of the tracks, County Line to Thatcher
 - b. Engineer report on file at the Village
 - c. Cost estimate to fix \$1,700,000
 - d. Grant application dated January, 2010.
2. Central Quadrant
 - a. Willow to UP tracks, County Line to cornfield
 - b. Engineer report on file at the Village.
 - c. Repaired blockage at Willow & Broadway
 - d. Repaired sewer collapse at Main & High St.
 - e. Cost estimate to fix balance \$1,400,000
 - f. Grant application dated January, 2010.
3. Ashton Avenue water diversion off Rt. 38 & cornfield
 - a. Engineer report on file at Village
 - b. Berms & landscape culverts have been removed
 - c. Estimated shared cost of \$9,000
4. Town home Detention Problem
 - a. Paid Baxter-Woodman to survey detention area and provide markers
 - b. Baxter-Woodman provided 3 cost estimates to mitigate standing water from \$27,000 to \$50,000
 - c. Homeowner's volunteered to cut drainage culvert through detention area to acquire flow to ditch.

B. Sewage Backup during Flood

1. Hired Baxter-Woodman to test all sewer manholes for leaks in all low-lying areas and to train Village personnel on proper testing procedures.
2. Replaced all lost or defective sewer clean-out caps, which allowed surface water infiltration into the sewer lines.
3. Noted several homes, which had diverted sub-pumps discharge lines directly into the sewer system.